



(12) **United States Patent**
Lasseter et al.

(10) **Patent No.:** **US 7,787,272 B2**
(45) **Date of Patent:** **Aug. 31, 2010**

(54) **INVERTER BASED STORAGE IN DYNAMIC DISTRIBUTION SYSTEMS INCLUDING DISTRIBUTED ENERGY RESOURCES**

5,329,222 A 7/1994 Gyugyi et al.
5,536,976 A 7/1996 Churchill

(Continued)

(75) Inventors: **Robert H. Lasseter**, Madison, WI (US);
Paolo Piagi, Woburn, MA (US)

FOREIGN PATENT DOCUMENTS

EP 1286444 2/2003

(Continued)

(73) Assignee: **Wisconsin Alumni Research Foundation**, Madison, WI (US)

OTHER PUBLICATIONS

(*) Notice: Subject to any disclaimer, the term of this patent is extended or adjusted under 35 U.S.C. 154(b) by 540 days.

Lasseter, Robert, Kevin Tomsovic, and Paolo Piagi. "Scenarios for Distributed Technology Applications with Steady State and Dynamic Models of Loads and Micro-Sources," Consortium for Electric Reliability Technology Solutions. Apr. 14, 2000.

(Continued)

(21) Appl. No.: **11/681,024**

Primary Examiner—Gary L Laxton

(22) Filed: **Mar. 1, 2007**

Assistant Examiner—Nusrat J Quddus

(65) **Prior Publication Data**

(74) *Attorney, Agent, or Firm*—Bell & Manning, LLC

US 2008/0212343 A1 Sep. 4, 2008

(51) **Int. Cl.**

H02M 7/66 (2006.01)

H02M 7/68 (2006.01)

H02M 7/72 (2006.01)

H02M 7/757 (2006.01)

(52) **U.S. Cl.** **363/98; 363/79**

(58) **Field of Classification Search** **363/15, 363/19, 21.03, 21.15, 21.16, 39, 118, 74, 363/78, 79, 95, 97, 98; 318/798**

See application file for complete search history.

(56) **References Cited**

U.S. PATENT DOCUMENTS

4,096,394 A 6/1978 Ullmann et al.

4,315,163 A 2/1982 Bienville


5,041,959 A 8/1991 Walker

5,198,698 A 3/1993 Paul et al.

(57) **ABSTRACT**

A microsource is provided, which includes an inverter, an energy storage device, and a controller. The controller calculates a maximum frequency change for the inverter based on a first comparison between a first power set point and a measured power from the inverter. The first power set point is defined based on a charge level of the energy storage device. A minimum frequency change for the inverter is calculated based on a second comparison between a second power set point and the measured power from the inverter. An operating frequency for the inverter is calculated based on a third comparison between a power set point and a measured power flow. A requested frequency for the inverter is calculated by combining the maximum frequency change, the minimum frequency change, and the operating frequency. The requested frequency is integrated to determine a phase angle of a voltage of the inverter to control a frequency of an output power of the inverter.

21 Claims, 11 Drawing Sheets



US 7,787,272 B2

Page 2

U.S. PATENT DOCUMENTS

5,559,704 A 9/1996 Vanek et al.
5,563,802 A 10/1996 Plahn et al.
5,596,492 A 1/1997 Divan et al.
5,614,770 A 3/1997 Suelzle
5,710,699 A 1/1998 King et al.
5,745,356 A 4/1998 Tassitino et al.
5,811,960 A 9/1998 Van Sickle et al.
6,014,015 A 1/2000 Thorne et al.
6,111,764 A 8/2000 Atou et al.
6,134,124 A 10/2000 Jungreis et al.
6,172,432 B1 1/2001 Schnackenberg et al.
6,188,205 B1 2/2001 Tanimoto et al.
6,219,591 B1 4/2001 Vu et al.
6,219,623 B1 4/2001 Wills
6,249,411 B1 6/2001 Hemena et al.
6,252,310 B1 6/2001 Wilhelm
6,285,917 B1 9/2001 Sekiguchi et al.
6,288,456 B1 9/2001 Cratty
6,347,027 B1 2/2002 Nelson et al.
6,356,471 B1 3/2002 Fang
6,359,423 B1 3/2002 Noro
6,465,910 B2 10/2002 Young et al.
6,693,809 B2 2/2004 Engler
6,787,933 B2 9/2004 Claude et al.
6,812,586 B2 11/2004 Wacknow et al.
6,870,279 B2 3/2005 Gilbreth et al.
7,042,110 B2 5/2006 Mikhail et al.
7,069,673 B2 7/2006 Kagoshima et al.

7,116,010 B2 10/2006 Lasseter et al.
2003/0036806 A1 2/2003 Schienbein et al.
2004/0051387 A1 * 3/2004 Lasseter et al. 307/80
2004/0080165 A1 4/2004 Geis et al.
2006/0208574 A1 9/2006 Lasseter et al.

FOREIGN PATENT DOCUMENTS

EP 1383224 1/2004

OTHER PUBLICATIONS

DOE News, The DER Weekly, vol. 2, No. 10, pp. 1-4, Mar. 9, 2001.
Lasseter, Robert, et al. "White Paper on Integration of Distributed Energy Resources the CERTS MicroGrid Concept," Consortium for Electric Reliability Technology Solutions, pp. 1-27, Apr. 2002.
Lasseter, Robert, "MicroGrids," IEEE, No. 0-7803-7322-7, pp. 305-308, Jul. 2002.
PCT International Search Report for PCT/US2008/054566 dated Jul. 11, 2008.
PCT International Search Report for PCT/US2008/054572 dated Jul. 11, 2008.
PCT International Search Report for PCT/US2008/054577 dated Jul. 11, 2008.
Son, Kwang, et al., "A Newton-Type Current Injection Model of UPFC for Studying Low-Frequency Oscillations," Power Engineering Society General Meeting, IEEE vol. 4, Jul. 13-17, 2003. (Abstract).
Notice of Allowance issued in U.S. Appl. No. 11/681,014 mailed July 30, 2009.

* cited by examiner






Fig. 1






Fig. 4






Fig. 5






Fig. 8




Fig. 9




Fig. 10




Fig. 11




Fig. 12




Fig. 13

1

INVERTER BASED STORAGE IN DYNAMIC DISTRIBUTION SYSTEMS INCLUDING DISTRIBUTED ENERGY RESOURCES

REFERENCE TO GOVERNMENT RIGHTS

This invention was made with United States government support awarded by the following agencies: National Science Foundation, Electrical & Communications System Div., Award No. 0078522. The United States government has certain rights in this invention.

FIELD

The field of the disclosure relates generally to power systems. More specifically, the disclosure relates to energy storage usage in an inverter based distributed energy resource included in a dynamic distribution system.

BACKGROUND

The demand for electrical power continues to grow worldwide. At the same time, aging transmission and distribution systems remain subject to occasional failures. Massive failures covering wide geographical areas and affecting millions of people have occurred, even in the United States, which has historically enjoyed a relatively reliable electrical power system. Problems with the capacity and reliability of the public power grid have driven the development of distributed energy resources (DER), small independent power generation systems which may be owned by, and located near, consumers of electrical power. DERs include a wide range of technologies, such as internal combustion engines, gas turbines, micro-turbines, photovoltaic cells, fuel cells, wind-power, storage systems, etc.

DERs can provide reliable power in critical applications as a backup to the primary electrical supply. For example, an interruption of power to a hospital can have life-threatening consequences. Similarly, when power to a factory is interrupted, productivity is lost, materials in process are wasted, and other costs are incurred in association with restarting the production line. Additionally, power from a DER can be provided to the main power grid to reduce energy price peaks by arbitraging energy price differentials. Geographically distributed sources of power, such as wind, solar, or hydroelectric power, may be too limited or intermittent to be used as the basis for a centralized power plant. However, these types of power sources can supplement or replace conventional power sources when the main power grid is available and can provide a backup when the main power grid is unavailable to increase energy efficiency and to reduce pollution and greenhouse gas emissions through the use of combined heat and power DER systems. DERs also can be used to meet load growth requirements and to enhance the robustness of the transmission system with a minimal addition of new lines.

Generally speaking, DERs can include two broad categories of electrical power sources: Direct current (DC) sources, such as fuel cells, solar cells, and batteries; and high-frequency analog current (AC) sources, such as micro-turbines and wind turbines. Both types of sources are typically used to provide an intermediate DC voltage, that may be produced directly by DC sources, and produced indirectly from AC sources, for example by rectification. In both types of sources, the intermediate DC voltage is subsequently converted to AC voltage or current at the required frequency, amplitude, and phase angle for use. In most cases, the conversion from the intermediate DC voltage to the usable AC voltage is per-

2

formed by a voltage inverter that can rapidly control the magnitude and phase of its output voltage.

DERs may be designed to operate in one of two modes: (1) "isolation" or "island" mode, wherein the DER is isolated from the main grid, and (2) normal "grid" mode, wherein the DER is connected to the main grid to either import power from or export power to the main grid. Smooth and efficient transition between the two modes is a necessity to effectively integrate DERs into the distribution system without harming the integrity of the remaining system. A centralized electrical power utility is in a position to monitor and coordinate the production and distribution of power from multiple generators. In contrast, DERs may include independent producers of power who have limited awareness or communication with each other. Even if the independent producers of power are able to communicate with each other, there may not be an effective way to ensure that they cooperate. As a result, to realize the potential of integrating DERs into the distribution system, the integration should not depend on complex, centralized command and control systems. Thus, for effective integration of DERs into the distribution system, a method and a system capable of responding to events in a distribution system using only local information is needed.

Effective integration of DERs into the distribution system also benefits from fast acting energy sources, such as storage, which provide the energy required by the loads until slower sources ramp-up their energy output when a DER isolates from the distribution system. Storage sources also allow the exploitation of energy price differentials by charging of the DER when power costs are low (i.e. at night) and discharging of the DER when power costs are high (i.e. during peak loads). Additionally, storage within an intermittent renewable such as a wind and/or a solar system can discharge when the renewable energy is low (no wind or sun) and charge when there is excess renewable energy (high wind at 2 a.m.). Thus, what is further needed is a method and a system capable of effective utilization of power and/or energy storage resources within a DER system.

SUMMARY

A method and a system for effective utilization of power and/or energy storage resources within a DER system are provided in an exemplary embodiment. Each active component of the distribution system reacts to local information such as a voltage, a current, and a frequency to correctly change its operating point.

In an exemplary embodiment, a controller for controlling a charge and/or a discharge of an energy storage device used in a distributed energy resource is provided. The controller calculates a maximum frequency change for the inverter based on a first comparison between a first power set point and a measured power from the inverter. The first power set point is defined based on a charge level of the energy storage device. A minimum frequency change for the inverter is calculated based on a second comparison between a second power set point and the measured power from the inverter. An operating frequency for the inverter is calculated based on a third comparison between a power set point and a measured power flow. A requested frequency for the inverter is calculated by combining the calculated maximum frequency change, the calculated minimum frequency change, and the calculated operating frequency. The calculated requested frequency is integrated to determine a phase angle of a voltage of the inverter to control a frequency of an output power of the inverter.

3

In an exemplary embodiment, a microsource is provided. The microsource includes an inverter, an energy storage device operably coupled with the inverter, and a controller operably coupled with the energy storage device and the inverter. The controller calculates a maximum frequency change for the inverter based on a first comparison between a first power set point and a measured power from the inverter. The first power set point is defined based on a charge level of the energy storage device. A minimum frequency change for the inverter is calculated based on a second comparison between a second power set point and the measured power from the inverter. An operating frequency for the inverter is calculated based on a third comparison between a power set point and a measured power flow. A requested frequency for the inverter is calculated by combining the calculated maximum frequency change, the calculated minimum frequency change, and the calculated operating frequency. The calculated requested frequency is integrated to determine a phase angle of a voltage of the inverter to control a frequency of an output power of the inverter.

In another exemplary embodiment, a method of controlling a charge and/or a discharge of an energy storage device used in a distributed energy resource is provided. A maximum frequency change for the inverter is calculated based on a first comparison between a first power set point and a measured power from the inverter. The first power set point is defined based on a charge level of the energy storage device. A second frequency change for the inverter is calculated based on a second comparison between a minimum power set point and the measured power from the inverter. An operating frequency for the inverter is calculated based on a third comparison between a power set point and a measured power flow. A requested frequency for the inverter is calculated by combining the calculated maximum frequency change, the calculated minimum frequency change, and the calculated operating frequency. The calculated requested frequency is integrated to determine a phase angle of a voltage of the inverter to control a frequency of an output power of the inverter.

Other principal features and advantages of the invention will become apparent to those skilled in the art upon review of the following drawings, the detailed description, and the appended claims.

BRIEF DESCRIPTION OF THE DRAWINGS

Exemplary embodiments of the invention will hereafter be described with reference to the accompanying drawings, wherein like numerals denote like elements.

FIG. 1 depicts a block diagram of a distributed energy resource system in accordance with an exemplary embodiment.

FIG. 2 is a diagram of a microgrid that includes a microsource implementing a unit power control scheme in accordance with an exemplary embodiment.

FIG. 3 is a diagram of a microgrid that includes a microsource implementing a zone power control scheme in accordance with an exemplary embodiment.

FIG. 4 is a graph depicting the relationship between steady state unit power vs. frequency ($P-\omega$) for two exemplary microsources having different loads for use in a unit power control scheme in accordance with an exemplary embodiment.

FIG. 5 is a graph depicting the relationship between steady state zone power vs. frequency ($F-\omega$) for two exemplary microsources having different loads for use in a zone power control scheme in accordance with an exemplary embodiment.

4

FIG. 6 is a diagram of two microsources used in a single zone in accordance with an exemplary embodiment.

FIG. 7 is a diagram of two microsources used in multiple zones in accordance with an exemplary embodiment.

FIG. 8 is a block diagram of an energy storage control system for a distributed energy resource in accordance with an exemplary embodiment.

FIG. 9 is a block diagram of a voltage regulator of the energy storage control system of FIG. 8 in accordance with an exemplary embodiment.

FIG. 10 is a graph depicting a sliding window for applying storage power limits in accordance with an exemplary embodiment.

FIG. 11 is a block diagram of a $P-\alpha$ droop controller of the energy storage control system of FIG. 8 in accordance with an exemplary embodiment.

FIG. 12 is a block diagram of a combined energy and power storage control system for a distributed energy resource in accordance with an exemplary embodiment.

FIG. 13 is a graph of an exemplary voltage droop regulation characteristic for a voltage regulator in accordance with an exemplary embodiment.

DETAILED DESCRIPTION

With reference to FIG. 1, a distributed energy resource (DER) system 100 is shown in accordance with an exemplary embodiment. Such an exemplary system is described, for example, in U.S. Pat. No. 7,116,010 and/or in U.S. Patent Publication No. 2006/000208574, the contents of which are incorporated by reference. Where the disclosure of the present application is limited by or in conflict with the disclosures of U.S. Pat. No. 7,116,010 and U.S. Patent Publication No. 2006/000208574, the disclosure of the present application controls. DER system 100 may include a utility supply 102 connected to a feeder line 104 that interconnects one or more microsource systems 106a, 106b, 106c, and 106d and one or more loads 108a, 108b, and 108c. DER system 100 may include a plurality of feeder lines. Feeder line 104, the one or more microsource systems 106a, 106b, 106c, and 106d, and the one or more loads 108a, 108b, and 108c can form a microgrid 110. Utility supply 102 can connect microgrid 110 to other similar microgrids distributed throughout DER system 100. A microsource system can include exemplary microsource power sources, power storage, and power controllers. The power source can be, for example, a fuel cell, hydroelectric generator, photovoltaic array, windmill, micro-turbine, etc. The power storage, if present, can be, for example, a battery or flywheel.

Feeder line 104 may include one or more interface switches. An exemplary interface switch is described, for example, in U.S. patent application Ser. No. 11/266,976, filed Nov. 4, 2005 and entitled INTERFACE SWITCH FOR DISTRIBUTED ENERGY RESOURCES, the contents of which are incorporated by reference. Where the disclosure of the present application is limited by or in conflict with the disclosure of U.S. patent application Ser. No. 11/266,976, the disclosure of the present application controls. The interface switch, if used, can be positioned between feeder line 104 and utility supply 102 so that microgrid 110 can be isolated from utility supply 102. When microgrid 110 is isolated from utility supply 102, the microgrid 110 is said to be operating in "island mode". When microgrid 110 is connected to the utility supply 110, the microgrid 110 is said to be operating in "grid mode". When DER system 100 is connected to the grid,

5

the one or more loads **108a**, **108b**, and **108c** may receive power from both the grid and local sources, depending on the current situational demands.

When a microsource or microgrid operates in island mode, load tracking problems can arise because typical power sources used in microsourses, such as microturbines or fuel cells, tend to respond slowly, with time constants ranging from 10 to 200 seconds. Additionally, these types of power sources may be inertialess. Conventional utility power systems store energy in the inertia of the spinning mass of a generator. When a new load comes online, the initial energy balance can be met by the system's inertia, which results in a slight reduction in system frequency. Because power sources in microsourses may be inertialess, a microsource may include power storage to ensure initial energy balance when loads are added during island mode.

Each microsource system **106a**, **106b**, **106c**, and **106d** preferably includes a microsource controller. The microsource controller responds to events using local information to respond to voltage drops, faults, blackouts, etc. and to switch to island operation mode as needed. The microsource controller controls the change in the output power of the system components as they change from a dispatched power mode to one in which frequency is controlled and load following is provided. Control schemes for a power controller in DER system **100** can be classified into one of three broad classes: unit power control, zone power control, and a mixed system using both unit power control and zone power control. Using a unit power controller, load changes are matched by a corresponding power injection from the utility because a microsource holds its injection to a set point P_0 . During island mode, the microsource matches the power demand as loads change. Each microsource system **106a**, **106b**, **106c**, and **106d** regulates the voltage magnitude at its connection point and the injected power using either a variable slope method or a fixed slope method.

Using a zone power controller, power flow in zones is controlled instead of controlling the power flow from each microsource. Each microsource system **106a**, **106b**, **106c**, and **106d** regulates the voltage magnitude at its connection point and the power that is flowing in the feeder. Using a zone power controller, the microsource systems **106a**, **106b**, **106c**, and **106d** pick-up extra load demands, and as a result, show a constant load to the utility grid. In this case, DER system **100** becomes a true dispatchable load as seen from the utility side supporting demand-side management arrangements. To reduce confusion, the symbol, F , is used for power flow in a zone and the symbol, P , is used for the power output from a microsource. When connected to the grid, load changes are matched by a different power injection from the microsource because the controller holds the flow of power coming from the grid, F_{line} , to a constant value. During island mode, all of the microsourses participate in matching the power demand as loads change.

With reference to FIG. 2, a diagram of a microgrid **200** is shown in accordance with an exemplary embodiment using a unit power controller. Microgrid **200** may include a microsource **202** and a load **108**. Microsource **202** may be connected to feeder line **104** by an inductor **204**. An interface switch may be provided, for example, in feeder line **104**. The interface switch can be opened to isolate microgrid **200** from the rest of DER system **100** and can be closed to connect microgrid **200** to the rest of DER system **100**. Microsource **202** may include a controller capable of measuring a current through inductor **204** and of measuring a system voltage at a point **206** in feeder line **104** where inductor **204** joins feeder line **104**.

6

With reference to FIG. 3, a diagram of a microgrid **300** is shown in accordance with an exemplary embodiment using a zone power controller. Microgrid **300** may include a microsource **302** and load **108**. Microsource **302** may be connected to feeder line **104** by inductor **204**. An interface switch may be provided, for example, in feeder line **104**. The interface switch can be opened to isolate microgrid **300** from the rest of DER system **100** and can be closed to connect microgrid **300** to the rest of DER system **100**. Microsource **302** may include a controller capable of measuring a current at a point **304** in feeder line **104** between utility supply **102** and inductor **204** and of measuring a system voltage at a point **206** in feeder line **104** where inductor **204** joins feeder line **104**.

With reference to FIG. 4, a graph depicting the relationship between steady state unit power and frequency ($P-\omega$) using a fixed minimum slope method and unit power control is shown in accordance with an exemplary embodiment. FIG. 4 shows steady state characteristics. The response may deviate from the characteristic during a transition period. Two exemplary microsourses included in the microgrid are shown. The microsourses have different power set points though this is not required. A first microsource has a first power set point **402**. A second microsource has a second power set point **404**. First power set point **402** and second power set point **404** are the amount of power injected by each source when connected to the grid at a system frequency ω_o . A constant slope

$$m = -\frac{\Delta\omega}{P_{max}}$$

allows power to change between $P=0$ and $P=P_{max}$ as frequency changes over $\Delta\omega$. A lower bounding line **400** extends from $P=0$ to $P=P_{max}$ with a starting frequency of ω_o . An upper bounding line **401** extends from $P=0$ to $P=P_{max}$ with a starting frequency of $\omega_o+\Delta\omega$. Because a constant slope is used by the controller, the response lines are all parallel to and extend between lower bounding line **400** and upper bounding line **401**.

Movement along the lines of constant slope m in response to a transition to island mode depends on whether or not the microgrid is importing power from or exporting power to the grid. If the system was exporting to the grid before islanding, the resulting frequency of ω_{exp} **412** is greater than the system frequency ω_o . For example, if the system was exporting to the grid before islanding, the second microsource may move from the system frequency ω_o at second power set point **404** to a third power set point **410** operating at ω_{exp} **412**. The first microsource may shift from the system frequency ω_o at first power set point **402** to a fourth power set point **406** at $P=0$. When the $P=0$ limit is reached, the slope of the characteristic is switched to vertical, as shown by the arrows, to move the first microsource frequency upwards to a fifth power set point **408** operating at ω_{exp} **412**. The specific set points, of course, depend on the local demands and operating points of the microsourses. A $P=0$ limit may not be reached by either microsource.

If the system was importing from the grid before islanding, the resulting frequency of ω_{imp} **420** will be smaller than the system frequency ω_o . For example, if the system was importing to the grid before islanding, the first microsource may move from the system frequency ω_o at first power set point **402** to a sixth power set point **414** operating at ω_{imp} **420**. The second microsource may move from the system frequency ω_o at second power set point **404** to a seventh power set point **416**

7

at $P=P_{max}$. When the $P=P_{max}$ limit is reached, the slope of the characteristic is switched to vertical, as shown by the arrows, to move the second microsource frequency downwards to an eighth power set point **418** operating at ω_{imp} **420**. The minimum and maximum power limits are enforced by switching the characteristic with constant slope to a vertical steady state characteristic when the minimum or maximum power limit is reached. The specific set points, of course, depend on the local demands and operating points of the microsourses. A $P=P_{max}$ limit may not be reached by either microsource.

With reference to FIG. 5, a graph depicting the relationship between steady state zone power and frequency ($F-\omega$) using a fixed minimum slope method and zone power control is shown in accordance with an exemplary embodiment. Two exemplary microsourses are included in the microgrid. The microsourses have different power set points. A first microsource has a first flow set point **500**. A second microsource has a second flow set point **502**. The slope is fixed at the minimum slope m , but has a reversed sign because of the relation between the microsource output power, P , and the zone power flow, F , which can be derived by inspection of FIG. 3 as $F_{line}+P_{source}=Load$. F_{line} is the power (imported means positive) from the rest of DER system **100**, and P_{source} is the power injected or absorbed by microsource **302**. The power injected or absorbed by microsource **302** is assumed: to be greater than the minimum power output, P_{min} , of microsource **302** and less than the maximum power output, P_{max} , of microsource **302**. For a microsource capable of power injection only, P_{min} is positive or zero, while a bidirectional device capable of both power injection or power storage may have $P_{min}<0$. Load is the overall loading level seen by microsource **302**.

During connection with the grid, the flow in the zones tracks the requested values at the system frequency ω_o . When the microgrid transfers to island mode, the two microsourses readjust the flow depending on the arrangement of the microsourses with respect to each other and utility supply **102**. When regulating unit power, the relative location of loads and microsourses is irrelevant, but when regulating zone power flow, the relative location of loads and microsourses is important. For example, with reference to FIG. 6, a first microsource **604** and a second microsource **610** are arranged in series in a single zone. The use of a single zone is for illustrative purposes only. There can be a greater or a lesser number of microsourses in a single zone.

The zone includes a first load **606** and a second load **612** on a local power bus **614** connected by an interface switch **600** to utility supply **102**. During a transition to island mode, interface switch **600** opens. As a result, in a zone power control method for the circuit of FIG. 6, a first flow **602** nearest to the utility system is zero in island mode. A second flow **608** may increase to compensate for the first flow **602** transition to zero. Thus, with reference to FIG. 5, first flow **602** moves from the system frequency ω_o at first flow set point **500** to a third flow set point **510** operating at the frequency ω_{exp} **514**. Second flow **608** moves from the system frequency ω_o at second flow set point **502** to a fourth power set point **512**. As a result, in island mode, the system operates at frequency ω_{exp} **514** where first flow **602** is zero. Frequency ω_{exp} **514** is larger than the nominal system frequency ω_o because the system was exporting to the grid (first flow **602**<second flow **608**), which is the same behavior seen using unit power control.

With reference to FIG. 7, a first microsource **706** and a second microsource **710** are arranged in parallel in two zones. The use of two zones each with a single microsource is for illustrative purposes only. There can be a greater or a lesser number of microsourses in a greater or a lesser number of

8

zones. A first load **708** is located on a first local power bus **714** connected by an interface switch **700** to utility supply **102**. A second load **712** is located on a second local power bus **716** connected by interface switch **700** to utility supply **102**. A first flow **702** flows through first local power bus **714**, and a second flow **704** flows through second local power bus **716**. The grid flow is the algebraic sum of first flow **702** and second flow **704**. During a transition to island mode, interface switch **700** opens.

In a zone power control method for the arrangement of FIG. 7, during island mode, the frequency takes the value where the sum of the flows is zero. As a result, as shown on FIG. 5, the frequency in island mode is frequency ω_{par} **508** where $F1=-F2$. With reference to FIG. 5, first flow **702** moves from the system frequency ω_o at first flow set point **500** to a fifth flow set point **504** operating at the frequency ω_{par} **508**. Second flow **704** moves from the system frequency ω_o at second flow set point **502** to a sixth power set point **506** at the frequency ω_{par} **508**.

With reference to FIG. 8, a microsource system **800** including an energy storage device **860** is shown in accordance with an exemplary embodiment. Microsource system **800** and its various components may be implemented in or include hardware, firmware, software, and/or any combination of these methods. Thus, microsource system **800** may include circuitry that can implement the processes indicated in the form of hardware, firmware, and/or a processor executing instructions embodied in software. Microsource system **800** connects to a grid through feeder lines **802**. Feeder lines **802** extend toward utility supply **102** in a first direction **804** and away from utility supply **102** in a second direction **806**. Microsource system **800** connects to feeder lines **802** through bus lines **803**. Microsource system **800** may include an inductor **824**, a transformer **850**, an inverter **852**, a voltage regulator **854**, a $P-\omega$ droop controller **856**, a charging coordinator **858**, and energy storage device **860**.

A first sensor **808** measures a feeder current **814** through feeder lines **802** and transmits the measured feeder current to $P-\omega$ droop controller **856**. A second sensor **810** measures a feeder bus voltage at the connection point of bus lines **803** with feeder lines **802**, transmits the measured feeder bus voltage **816** to voltage regulator **854**, and transmits the measured feeder bus voltage **818** to $P-\omega$ droop controller **856**. A third sensor **812** measures an inverter current through bus lines **803** between transformer **850** and feeder lines **802**, transmits the measured inverter current **820** to voltage regulator **854**, and transmits the measured inverter current **822** to $P-\omega$ droop controller **856**.

Inverter **852** connects to feeder lines **802** through inductance **824** and transformer **850**. Inverter **852** generates an output voltage at a phase angle of δ . In general, the magnitude of δ is small enough to satisfy the approximation $\sin(\delta)\sim\delta$. This implies that power is linear relative to δ . Voltage regulator **854** assists in decoupling interactions between DER microsourses and includes a voltage vs. reactive power droop controller so that, as the reactive power Q generated by the inverter becomes more capacitive, a local voltage set point **826** is reduced. Conversely, as Q becomes more inductive, local voltage set point **826** is increased. $P-\omega$ droop controller **856** provides the $P-\omega$ and/or $F-\omega$ functions described with reference to FIGS. 4 and 5. $P-\omega$ droop controller **856** additionally provides control over energy storage device **860** using information from charging coordinator **858**. Charging coordinator **858** controls the rate of charge and discharge and the charge levels of energy storage device **860** by setting

power output limits on P- ω droop controller **856**. Energy storage device **860** connects with inverter **852** through a DC bus **842**.

With reference to FIG. 9, a block diagram of voltage regulator **854** is shown in accordance with an exemplary embodiment. Voltage regulator **854** may include a Q measured block **900**, a β block **902**, a magnitude block **904**, and a controller **906**. The local voltage set point **826** is input to voltage regulator **854**. A regulated output voltage **828** is output from voltage regulator **854** and input to inverter **852**. Creating an appropriate regulated output voltage at the terminals of inverter **852** regulates the feeder bus voltage. A reactive power **912** is calculated in Q measured block **900** using the measured feeder bus voltage **816** and the measured inverter current **820** as inputs. The calculated reactive power **912** is input to a β block **902**, which calculates a modified reactive power **914**. The modified reactive power **914** is subtracted from local voltage set point **826** in a summer **908** to define a desired local voltage set point **916** based on a droop constant β defined in β block **902**. In an exemplary embodiment, β block **902** is implemented to exhibit a voltage vs. reactive current droop as shown with reference to FIG. 13. Droop constant β is the slope of the droop characteristic line **1300**. As reactive power Q becomes more inductive, the desired local voltage set point **916** becomes larger than the local voltage set point **826**. As reactive power Q becomes more capacitive, the desired local voltage set point **916** becomes smaller than the local voltage set point **826**.

The magnitude **918** of the measured feeder bus voltage **816** is determined in magnitude block **904**. The magnitude **918** of the measured feeder bus voltage **816** is compared to the desired local voltage set point **916**. For example, a summer **910** subtracts the magnitude **918** of the measured feeder bus voltage **816** from the desired local voltage set point **916**. The resulting voltage error **920** is input to controller **906** to generate the regulated output voltage **828**. In an exemplary embodiment, controller **906** is a proportional-integral controller.

Energy storage device **860** normally operates in flow control mode with a F- ω characteristic as shown in FIG. 5. In some situations, energy storage device **860** may operate in unit power control mode with a P- ω characteristic as shown in FIG. 4. In either case, the limits of power from energy storage device **860** are used. With reference to FIG. 10, the range of output power, P, available from energy storage device **860** imposes a window **1007** on feeder flow, F, such that $P_{load} - P_{max} < F < P_{load} - P_{min}$, where P_{load} is the load on the system, and P_{max} and P_{min} are the limits on energy storage device **860**. When charging, P_{min} is negative. A system F- ω operating point **1000** is defined for the system frequency ω_o . The limits for the feeder flow, F, can be visualized on the F- ω plane as a window whose width **1006** is the difference between F_{min} **1002** and F_{max} **1004** which equals the difference between P_{max} and P_{min} . The location of the window on the F-axis depends on the value of P_{load} . As P_{load} increases, window **1007** slides to the right on the F- ω plane. Conversely, if the load is reduced, window **1007** slides to the left on the F- ω plane.

An example flow set point **1008** falls within window **1007**. Situations are possible that can result in the flow set point falling outside window **1007**. For example, load levels while connected to the grid, an incorrect choice for the flow set point, a change in output power of other microsources, and a transfer to island mode all can cause the flow set point to fall outside window **1007**. For example, a first flow set point **1010** falls to the left of window **1007**. In this situation, P_{max} is exceeded. As another example, a second flow set point **1012**

falls to the right of window **1007**. In this situation, P_{min} is exceeded. To avoid a flow set point falling outside window **1007**, when the flow set point is outside window **1007**, the controls reset the flow set point to the closest edge of window **1007**.

With reference to FIG. 11, P- ω droop controller **856** is shown in accordance with an exemplary embodiment. P- ω droop controller **856** may include a P measure block **1100**, a first summer **1102**, a first proportional-integral (PI) controller **1104**, a second summer **1106**, a second PI controller **1108**, an F measure block **1110**, a third summer **1112**, a multiplier **1114**, a fourth summer **1116**, a fifth summer **1118**, and an integrator **1120**. Inputs of P- ω droop controller **856** include the measured inverter current **822**, the measured feeder current **814**, and the measured feeder bus voltage **818**. With reference to FIG. 8, inputs of P- ω droop controller **856** also include power limits **834** from charging coordinator **858**, a power set point **830**, and a frequency set point **832**. Outputs of P- ω droop controller **856** include an inverter phase angle **836** input to inverter **852** and a P_{meas} **838** input to charging coordinator **858**.

With reference to FIG. 11, P- ω droop controller **856** may be used to provide zone power control or unit power control. As a result, power set point **830** may be P_o or F_o and a power flow **1148** input to third summer **1112** may be F_{meas} **1132** or P_{meas} **838**. Inputs of F measure block **1110** include the measured feeder current **814** and the measured feeder bus voltage **818**. F measure block **1110** outputs F_{meas} **1132**. Inputs of P measure block **1100** include the measured inverter current **822** and the measured feeder bus voltage **818**. P measure block **1100** outputs P_{meas} **838** to first summer **1102** and second summer **1106**. If unit power control is used, P measure block **1100** outputs P_{meas} **838** to third summer **1112**. If unit power control is used, the sign of slope m in multiplier block **1114** is reversed. F measure block **1110** outputs F_{meas} **1132** to third summer **1112** if zone power control is used.

Power limits **834** include a P_{max} set point **1134** of energy storage device **860** and a P_{min} set point **1140** of energy storage device **860**. Changing the limits P_{max} and P_{min} controls the width of window **1007** shown with reference to FIG. 10. Charging coordinator **858** controls the charge state of energy storage device **860** through the limits P_{max} and P_{min} . First summer **1102** compares P_{max} set point **1134** with P_{meas} **838** to calculate a first power difference **1136** input to first PI controller **1104**. For example, first summer **1102** subtracts P_{meas} **838** from P_{max} set point **1134**. First PI controller **1104** controls the maximum power through a maximum frequency change **1138**, $\Delta\omega_{max}$, that is limited between a minimum frequency and 0 Hz. In an exemplary embodiment, the minimum frequency is -1 Hz. Second summer **1106** compares P_{min} set point **1140** with P_{meas} **838** to calculate a second power difference **1142** input to second PI controller **1108**. For example, second summer **1106** subtracts P_{meas} **838** from P_{min} set point **1140**. Second PI controller **1108** controls the minimum power through a minimum frequency change **1144**, $\Delta\omega_{min}$, that is limited between 0 Hz and a maximum frequency. In an exemplary embodiment, the maximum frequency is 1 Hz. $\Delta\omega_{max}$ and $\Delta\omega_{min}$ are scaled as radians for input to fifth summer **1118**. Maximum frequency change **1138** and minimum frequency change **1144** maintain the flow set point within window **1007**. In general, control parameters of the first and second PI controllers **1104**, **1108** are set such that a steady state at a limit is reached in 10-20 cycles.

Third summer **1112** compares power set point **830** with power flow **1148** to calculate a third power difference **1150** input to multiplier **1114**. For example, third summer **1112** subtracts power flow **1148** from power set point **830**. Multi-

11

plier 1114 multiplies third power difference 1150 by the slope m to determine a frequency change 1152. Depending on the type of power control, frequency change 1152 may be defined as $m(F_o - F_{meas})$ or $-m(P_o - P_{meas})$. Fourth summer 1116 adds frequency set point 832 to frequency change 1152 to calculate an operating frequency 1154 input to fifth summer 1118. Fifth summer 1118 adds operating frequency 1154 with maximum frequency change 1138 and minimum frequency change 1144 to calculate a requested frequency 1156 input to integrator 1120. The output of the integrator 1120 is inverter phase angle 836, which is rotating in time at frequency ω_{req} . Inverter phase angle 836 is reset to zero when it exceeds 2π radians.

With reference again to FIG. 8, charging coordinator 858 controls the rate of charge and discharge and the charge levels of energy storage device 860 by setting power limits 834 on P- ω droop controller 856. For example, if energy storage device 860 is fully charged, P_{max} set point 1134 is set to zero, forcing the power set point 830 to match the effective load. Charging coordinator 858 can be implemented, for example, using a look up table or an analog circuit. Inputs to charging coordinator 858 include a charge level and a storage power 840 of energy storage device 860 and P_{meas} 838 calculated by P- ω droop controller 856. The outputs are power limits 834 input to P- ω droop controller 856.

Control of energy storage device 860 utilizes two distinct parameters: 1) a storage power, P_s , that determines how fast energy can be extracted or injected into energy storage device 860, and 2) an energy level, E_s , that can be stored in energy storage device 860. The silicon devices in inverter 852 may have a thermal upper bound that limits the peak current capabilities to about 2 pu of their nominal rated value. The resulting peak current defines a parameter $\pm P_{peak}$. The output power from energy storage device 860 has a rating P_{dis} based on its preferred discharge rate and a rating P_{chg} based on its preferred charge rate. These maximum charge and discharge rates are used when the distribution system requires the highest available level of power. For example, when the system switches to island mode, the maximum discharge rate is needed until other microsources can provide the needed energy. Setting P_{min} and P_{max} in P- ω droop controller 856 enforces the required rate limits. For example, to fix the discharge rate at P_{dis} , P_{min} and P_{max} can be set to P_{dis} . As a result, the other microsources increase or decrease their output as the loads change. Alternatively, to fix the discharge rate at P_{dis} , P_{max} can be set to P_{dis} . As a result, energy storage device 860 tracks load changes without exceeding the ideal discharge rate, P_{dis} .

Charging coordinator 858 also enforces energy levels to avoid overcharging energy storage device 860 and to ensure enough power supply to loads during island mode for a determined period of time. Again, these limits are enforced by P_{min} and P_{max} . A minimum energy level E_{min} corresponds with an energy level at which energy storage device 860 can only be charged because there is no available energy. A maximum energy level E_{max} corresponds with an energy level at which energy storage device 860 can only be discharged because there is no available storage. A minimum reserve energy level E_{min_res} corresponds with the minimum reserve value of energy that energy storage device 860 maintains to provide short-term energy to loads during islanding. A maximum reserve energy level E_{max_res} corresponds with the maximum reserve value of energy that energy storage device 860 generally does not exceed except during a brief time in island operation.

Three main operating regions defined by E_{min} , E_{max} , E_{min_res} , and E_{max_res} dictate the behavior of charging coordinator 858.

12

In general, $E_{min} < E_{min_res} < E_{max_res} < E_{max}$. In a first storage region, between E_{min_res} and E_{max_res} , the energy is considered within normal values. In a second storage region, between E_{min} and E_{min_res} , energy storage device 860 is normally charged to a level between E_{min_res} and E_{max_res} , but can be discharged to balance power when islanding. In a third storage region, between E_{max_res} and E_{max} , energy storage device 860 is normally discharged to a level between E_{min_res} and E_{max_res} , but can be charged to balance power when islanding.

Energy storage device 860 has high energy requirements to allow transfer of energy from low load periods to peak periods and high power requirements for load tracking and power quality needs. In general, if a battery is optimized for energy applications, recurring power demands, such as islanding or power quality events, tend to cause premature failure. Battery systems for bulk energy applications use such technologies as flow batteries and high-temperature batteries (such as sodium-sulfur and sodium-metal chloride). These need to be able to have continuous discharge over a specific time period. At the other end of the spectrum are uninterruptible power supply (UPS) systems or power battery applications, which demand high power discharge in seconds. To support both energy storage and power storage functions, a plurality of storage devices may be mounted in parallel. The rate of power change could be controlled using a ramp filter in P- ω droop controller 856, which controls the rate of change of the requested frequency 1156, and therefore, the rate of power change.

Given the technology restrictions for different types of batteries, fly wheels, super-capacitors, etc., different parameters in energy E and rate of power P are needed, which directly impacts the lifetime of the technology. For example, if an application displaces energy from night to daytime loads, the rate of power input and output should be very small. Alternatively, if an application is used in a power mode, a different storage system is needed to allow fast discharge, in several cycles, to meet loss of generation. For all applications and storage systems, changing the power limits P_{min} and P_{max} continuously controls the rate of charge or discharge of energy storage device 860.

With reference to FIG. 12, a power storage system 1200 is connected to microsource system 800 in accordance with an exemplary embodiment to support high energy and high power requirements. Power storage system 1200 may include an energy storage controller 1202, a chopper controller 1204, a power storage device 1206, and a DC-DC chopper 1208. Power storage system 1200 connects to DC bus 842 between energy storage device 860 and inverter 852 through DC-DC chopper 1208. Power storage system 1200 provides a fast rate of energy, generally <1 second, to inverter 852. Energy storage controller 1202 controls the rate of discharge of energy storage device 860 by measuring a DC current 1212 drawn by inverter 852 from energy storage device 860. Energy storage controller 1202 further receives a ramp rate 1210 as an input to calculate an output current 1214. Output current 1214 is input to chopper controller 1204 as an injected current reference which holds the power rate from energy storage device 860 to a maximum power ramp rate.

Control of energy storage device 860 and power storage device 1206 is coordinated through various input parameters. The basic coordination is through the rate of charge or discharge. The discharge rate is provided by ramp rate 1210 through the energy storage controller. The charge rate is controlled by the limits provided by the charging coordinator 858. Additionally, ramp rate 1210 may reduce the need for continually changing the power limits input to P- ω droop

13

controller 856 and may remove the need to enforce a rate limit on inverter 852. The amount of power stored at power storage device 1206 may be dictated by the amount of power required to make up the difference between what is needed by inverter 852 and what can be provided by energy storage device 860.

The foregoing description of exemplary embodiments of the invention have been presented for purposes of illustration and of description. It is not intended to be exhaustive or to limit the invention to the precise form disclosed, and modifications and variations are possible in light of the above teachings or may be acquired from practice of the invention. The embodiments were chosen and described in order to explain the principles of the invention and as practical applications of the invention to enable one skilled in the art to utilize the invention in various embodiments and with various modifications as suited to the particular use contemplated. It is intended that the scope of the invention be defined by the claims appended hereto and their equivalents.

What is claimed is:

1. A controller for controlling a charge and/or a discharge of an energy storage device used in a distributed energy resource, the controller comprising circuitry:

to calculate a maximum frequency change for an inverter based on a first comparison between a first power set point and a measured power from the inverter, wherein the first power set point is defined based on a charge level of an energy storage device coupled to the inverter;

to calculate a minimum frequency change for the inverter based on a second comparison between a second power set point and the measured power from the inverter;

to calculate an operating frequency for the inverter based on a third comparison between a power set point and a measured power flow;

to calculate a requested frequency for the inverter by combining the calculated maximum frequency change, the calculated minimum frequency change, and the calculated operating frequency; and

to integrate the calculated requested frequency to determine a phase angle of a voltage of the inverter to control a frequency of an output power of the inverter.

2. The controller of claim 1, wherein calculating the operating frequency comprises use of $m(F_o - F)$, where m is a slope of an F - ω characteristic, F_o is the power set point, and F is the measured power flow.

3. The controller of claim 1, wherein calculating the operating frequency comprises use of $m(P_o - P)$, where m is a slope of a P - ω characteristic, P_o is the power set point, and P is the measured power flow.

4. The controller of claim 3, wherein the measured power is the measured power flow.

5. The controller of claim 1, wherein calculating the maximum frequency change comprises subtracting the measured power from the first power set point to determine a power differential.

6. The controller of claim 5, wherein calculating the maximum frequency change further comprises applying the determined power differential to a proportional-integral controller.

7. The controller of claim 1, wherein calculating the minimum frequency change comprises subtracting the measured power from the second power set point to determine a power differential.

8. The controller of claim 7, wherein calculating the minimum frequency change further comprises applying the determined power differential to a proportional-integral controller.

9. The controller of claim 1, wherein the second power set point is defined based on the charge level of the energy storage device.

14

10. The controller of claim 1, further comprising regulating an output voltage of the inverter using a voltage versus reactive power droop controller.

11. The controller of claim 1, wherein the first power set point is set to a maximum discharge rate of the energy storage device during a transition to island mode.

12. The controller of claim 1, wherein the first power set point is set to a preferred discharge rate of the energy storage device after a transition to island mode.

13. The controller of claim 12, wherein the second power set point is set to the preferred discharge rate of the energy storage device after the transition to island mode.

14. The controller of claim 1, wherein the first power set point is set to a preferred discharge rate of the energy storage device when an energy level of the energy storage device exceeds a maximum energy reserve level.

15. The controller of claim 1, wherein the first power set point is set to approximately zero when an energy level of the energy storage device falls below a minimum energy reserve level.

16. The controller of claim 1, further comprising measuring a current drawn by the inverter from the energy storage device.

17. The controller of claim 16, further comprising holding a power rate from the energy storage device to a maximum power ramp rate.

18. A method of controlling a charge and/or a discharge of an energy storage device used in a distributed energy resource, the method comprising:

calculating a maximum frequency change for an inverter using a controller based on a first comparison between a first power set point and a measured power from the inverter, wherein the first power set point is defined based on a charge level of an energy storage device coupled to the inverter;

calculating a minimum frequency change for the inverter using the controller based on a second comparison between a second power set point and the measured power from the inverter;

calculating an operating frequency for the inverter using the controller based on a third comparison between a power set point and a measured power flow;

calculating a requested frequency for the inverter using the controller by combining the calculated maximum frequency change, the calculated minimum frequency change, and the calculated operating frequency; and

integrating the calculated requested frequency to determine a phase angle of a voltage of the inverter to control a frequency of an output power of the inverter.

19. A microsource, the microsource comprising:

an inverter;

an energy storage device operably coupled with the inverter; and

a controller operably coupled with the energy storage device and the inverter, the controller including circuitry configured

to calculate a maximum frequency change for the inverter based on a first comparison between a first power set point and a measured power from the inverter, wherein the first power set point is defined based on a charge level of the energy storage device;

to calculate a minimum frequency change for the inverter based on a second comparison between a second power set point and the measured power from the inverter;

to calculate an operating frequency for the inverter based on a third comparison between a power set point and a measured power flow;

15

to calculate a requested frequency for the inverter by combining the calculated maximum frequency change, the calculated minimum frequency change, and the calculated operating frequency; and

to integrate the calculated requested frequency to determine a phase angle of a voltage of the inverter to control a frequency of an output power of the inverter.

20. The microsource of claim **19**, further comprising a power storage device operably coupled with the inverter, wherein the controller is operably coupled with the power

16

storage device and further includes circuitry configured to limit a power rate of the energy storage device and to control an amount of power output from the power storage device to the inverter.

21. The microsource of claim **20**, wherein the controller further includes circuitry configured to measure a current drawn by the inverter from the energy storage device to limit the power rate of the energy storage device.

* * * * *